

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,595-00-00

LEASE NAME Ramsey 'Z'

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #2

500' Ft. from S Section Line

660' Ft. from E Section Line

LEASE OPERATOR Slawson Exploration Co., Inc.

SEC. 30 TWP. 17S RGE. 30 (E) or (W)

ADDRESS 20 N. Broadway, Suite 700, Oklahoma City, OK 73102 COUNTY Lane

PHONE# (405) 232-0201 OPERATORS LICENSE NO. 3988'

Date Well Completed _____

Character of Well D&A

Plugging Commenced 8-6-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-6-91

The plugging proposal was approved on 8-6-91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Mississippian Depth to Top _____ Bottom _____ T.D. 4605'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	374'	None

SEP 06 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; set 1st plug @ 2300'-2100' w/50 sx; 2nd plug @ 1450'-1250' w/50 sx; 3rd plug @ 750'-630' w/30 sx; ; 4th plug @ 400'-200' w/50 sx; 5th plug @ 40'-surface w/10 sx; mousehole 10 sx; rathole 15 sx; Total 215 sx 60-40 posmix 6% gel # Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 91

Angela Woodard
Notary Public

My Commission Expires: March 20, 1993