

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-101-21814-60-00

LEASE NAME Dowd

WELL NUMBER #1

790 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 25 TWP. 17S RGE. 30 XXX (W)

COUNTY Lane

Date Well Completed 6/12/03

Plugging Commenced 6/12/03

Plugging Completed 6/12/03

RECEIVED
JUL 03 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188 Wichita, KS 67278-3188

PHONE#(316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/12/03 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4635'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	228'	8-5/8"	228'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
1st plug @ 2250' w/50 sx 60/40 pos, 6% gel with 1/4# floseal/sx. 2nd plug @ 1500' w/80 sx, 3rd plug @ 840' w/50 sx, 4th plug @ 240' w/40 sx, 5th plug @ 40' w/10 sx, 15 sx in rat hole. Total 245 sx.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick

John Niernberger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 2003

My Commission Expires: 5/4/2003

Notary Public



Form CP-4
Revised 05-83