

1 070947

5-15 00077-0000 63

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,439
C NE NE, SEC. 4, T. 17 S, R. 27 W
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293
Operator: Helmerich & Payne, Inc.
Name:
Address: P.O. Box 558
Garden City, KS 67846

Lease Name Leighton A Well # 1
County Lane 145.76
Well Total Depth 4485 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Helmerich & Payne, Inc. License Number 5293
Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 9 a.m. Day: 15 Month: 5 Year: 19 91

Plugging proposal received from Millard Lindsay

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 4 1/2" at 4275' w/240 sx cement, PBTD 4241', Perfs at 4029-64'
1st plug pump 100 lbs. hulls in 30 sx 60/40 Pozmix 6% gel displaced with gel from perfs to 0'

2nd plug perforate casing at 1250' and pump 150 sx cement down 4 1/2",

3rd plug pump 150 sx cement down backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls in 30 sx cement displaced with gel from perfs to 0',

2nd plug perforated casing at 1250' and pumped 150 sx cement down 4 1/2". Maximum pressure 750 psi and shut in 200 psi.

3rd plug pumped 150 sx cement down backside. Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 5-22-91

INV. NO. 31866

Signed Dan Goodrow (TECHNICIAN)
MAY 17 1991