

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20485-00-00
Spot: CS2SWSW Sec/Twnshp/Rge: 4-17S-27W
330 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: KUEHN Well Number: 2
County: LANE Total Vertical Depth: 4480 feet
Operator License No.: 32457
Conductor Pipe: Size feet: 145.60
Op Name: ABERCROMBIE ENERGY, LLC
Surface Casing: Size 8.625 feet: 307 WITH 185 SX CMT
Address: 150 N. MAIN, STE 801
Production: Size 4.5 feet: 4295 WITH 200 SX CMT
WICHITA, KS 67202
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/07/2003 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED ABERCROMBIE Company: ABBERCROMBIE ENERGY Phone: (316) 262-1841

Proposed Plugging Method: BOTTOM WITH 30 SX CMT WITH 200# HULLS & GEL BEHIND CMT TO 1200'. PERF 2 SHOTS 1200'. TOP PLUG WITH 200 SX CMT. PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/07/2003 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4295'. PERFS AT 4148-54 & 4174-80'. SQUEEZE AT 1735' WITH 250 SX CMT. OVERSHOT LEFT IN HOLE AT 2118'. RAN TUBING IN HOLE TO 2086'. PUMPED 4 SX GEL & 50 SX OF COMMON CMT WITH 3% CC WITH HULLS MIXED IN AT 150#. TOC @ 1400'. PULLED TUBING TO 1120'. LET SET TO GIVE BOTTOM PLUG TIME TO SET UP. PRESSURE TESTED 4 1/2" X 2 3/8" ANNULUS TO 600#. PERFORATED AT 1200'. PUMPED INTO AT 900# 2 BPM. PULLED TUBING OUT OF HOLE. PUMPED DOWN 4 1/2" 160 SX 60/40 POZMIX 6% GEL. MAXIMUM PRESSURE 900#. SHUT IN AT 725#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 65 SX CMT. MAXIMUM PRESSRE 600#. SHUT IN WITH 600#.

RECEIVED
JAN 23 2003
KCC WICHITA.

Remarks: USED COMMON CMT W/3% CC & 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED
JAN 14 2003
KCC Dodge City

Signed Kevin D Strube
(TECHNICIAN)
INVOICED
DATE 1-24-03
INV. NO. 2003061110