

1 051246

12-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. C SE SW, SEC. 30, T 17 S, R 30 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,534-00-00

TECHNICIAN'S PLUGGING REPORT

640 feet from S section line
3330 feet from E section line

Operator License # 3988

Lease Name Ramsey "W" Well # 1

Operator: Slawson Exploration Company, Inc.
Name &

County Lane 149.83

Address 104 South Broadway, Suite 200
Wichita, KS 67202-4165

Well Total Depth 4610 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 1 Month: 12 Year: 1989

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling (phone) 316-793-3851

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2895' GL
Anhydrite 2245-65'
1st plug at 2265' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,
3rd plug at 380' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 1 Month: 12 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 2265' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 380' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

(copy) did not observe this plugging.

DATE 1-5-89

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 26899

12-1

EFFECTIVE DATE: 11-13-89

FORM MUST BE TYPED
FORM C 1 12/88

State of Kansas 15-101-21,534-00-00

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. November .. 13 .. 1989 .. Ap. C. .. SE .. SW .. Sec 30 .. Twp 17 S, Rg 30 .. XX East
month day year

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 South Broadway, Suite 200
City/State/Zip: Wichita, Kansas 67202-4165
Contact Person: Bob Jenkins
Phone: (316) 263-3201

640' feet from South line of Section
3330' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC. K.K.I. Box 183 B.

316-793-3851

Great Bend KS 67530

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

County: LANE
Lease Name: RAMSEY "W" Well #: 1
Field Name: Wildcat
Is this a Prorated Field? ... yes no
Target Formation(s): MISSISSIPPIAN
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 2895' GR (Seis) feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 150' 180'
Depth to bottom of usable water: 1200'
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 340'
Length of Conductor pipe required: None
Projected Total Depth: 4600'
Formation at Total Depth: MISSISSIPPIAN

If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water Source for Drilling Operations:
Water well ... farm pond ... other
DWR Permit #: 889-045
Will Cores Be Taken?: ... yes no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location:


Exp. 5/8/90

spud 11-25-89 set 340'

AFFIDAVIT

200' Alt. II Req.

PUSHER Gregg Davidson
TD 4670 FORMATION
SURFACE PIPE 8 5/8 @ 349
ANHYDRITE 2245 ELEVATION 2895 GL
STARTING TIME & DATE 4pm 12-1
COMPLETION TIME & DATE 10pm 12-1
1st PLUG @ 2265 FT. WI 50 SX
2nd PLUG @ 1300 FT. WI 80 SX
3rd PLUG @ 380 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI _____ SX
WATER WELL PLUGGED WI _____ SX
CEMENT COMPANY Allard
TECHNICIAN R. L
TYPE OF CEMENT 60/40 p026%



spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.