

1 070839

8-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,555 -00-00
SW SE NE, SEC. 30, T. 17 S, R. 30 WR
2970 feet from S section line
990 feet from E section line
Lease Name Ramsey "X" Well # 1
County Lane 148.88
Well Total Depth 4581 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 371

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Operator: Slawson Exploration Company
Name & Address 104 S. Broadway, Suite 200
Wichita, KS 67202-4165

Well Total Depth _____ feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 24 Month: 8 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2245-65'
1st plug at 2270' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 400' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 24 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2270' with 50 sx cement,
2nd plug at 1400' with 80 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 400' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

AUG 28 1990

INVOICED
(If desired, observe this plugging.)

Signed Dan Johnson
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

DATE: 8-30-90
INV. NO. 29185
8-24

EFFECTIVE DATE: 8-5-90

State of Kansas

15-101-21,555-00-00

NOTICE OF INTENTION TO DRILL

Must be approved by the K.S.C. five (5) days prior to commencing well

Expected Spud Date ... August ... 10 ... 1990
month day year

SW. SE. NE. Sec. 30. Twp. 17. S, Rg. 30. East
 West

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 South Broadway, Suite 200
City/State/Zip: Wichita, Kansas 67202-4165
Contact Person: Robert B. Jenkins
Phone: (316) 263-3201

..... 2970' feet from South line of Section
..... 990' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC.

County: Lane
Lease Name: Ramsey "X" Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OMWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'

If OMWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Ground Surface Elevation: 2893' GR. (Seis.) feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location:
Exp. 1/31/91

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1150'
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 345'
Length of Conductor pipe required: None

Projected Total Depth: 4600'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
 well ... farm pond ... other

DWR Permit #: 17-400
Will Cores Be Taken?: ... yes no
If yes, proposed zone:

AFFIDAVIT

250' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Davidson INIT. MS

SPUD DATE 8-15-90 LENGTH SURFACE PLANNED 345'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 6 7/8 @ 371 CONDUCTOR _____
ANHYDRITE T- 2245 B- 2265 ELEVATION _____

TD 4580 FORMATION MISS

RAN PIPE @ _____ SX	DV TOOL _____ SX	ALT II DONE Y _____ N _____
Arbuckle Plug @ _____ Ft. W/ _____ SX		
Hug./Council @ _____ Ft. W/ _____ SX		
Anhydrite Base @ <u>2270</u> Ft. W/ <u>50</u> SX		
1/2 Base Anyh. @ <u>1400</u> Ft. W/ <u>80</u> SX		
1/2, 1/2 Plug @ <u>700</u> Ft. W/ <u>40</u> SX		
Bottom Surface @ <u>400</u> Ft. W/ <u>50</u> SX		
40' Plug @ <u>40</u> Ft. W/ <u>10</u> SX		

RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ _____ SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
TECHNICIAN C.H. DATE 8-23-90 Hauling _____

TYPE OF CEMENT _____ DATE 8-24-90

STARTING TIME / 3:30 (AM/PM) DATE 8-24-90

COMPLETION TIME 4:00 (AM/PM) DATE 8-24-90

CEMENT COMPANY Adler 60/40 1/4 H Flower
60/40 1/4 60/40

ADP