

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21652-00-00
Spot: NWSE Sec/Twnshp/Rge: 30-17S-30W
2080 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: CRAMER B Well Number: 1
County: LANE Total Vertical Depth: 4401 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet: 143.03
Surface Casing: Size 8.625 feet: 213 WITH 135 SX CMT
Production: Size 4.5 feet: 4395 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/31/2001 11:15 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES Phone: (316) 262-2502

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS FOR BOTTOM PLUG. SPACER TO 2260'. FILL TO SURFACE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/31/2001 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4370'. BP @ 4050'. PERFS AT 3959-62, 4101-04, 4246-48, 4008-11'. DV TOOL @ 2259' WITH 450 SX CMT. PUMP 25 SX CMT WITH 200# HULLS FOR BOTTOM PLUG. PUMP 9 SX GEL & 140 SX CMT. HOLE LOADED. TIED ONTO BACKSIDE AND PRESSURED UP TO 500# AND HELD.

RECEIVED

FEB - 5 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED-2 STAGED.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

INVOICED

JAN 18 2002

DATE

Feb 6-02

INV. NO.

2002061342