

1 060024

6-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,549-00-00

NE NE NW, SEC. 30, T 17 S, R 30 W/E

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Ramsey "Z" Well # 1

Operator: Slawson Exploration Company, Inc.
Name & Address 104 S. Broadway, Suite 200

County Lane 149.11

Wichita, KS 67202-4165

Well Total Depth 4588 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2:30 a.m. Day: 26 Month: 6 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2255-75'

1st plug at 2280' with 50 sx cement, 2nd plug at 1400' with 50 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 375' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6 a.m. Day: 26 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,

2nd plug at 1400' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 375' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

I (XXXX) did not observe this plugging.

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 7-3-90
BILL NO. 28543
6-26

