

1 080265

To:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,079 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.

Name &

Address 300 West Douglas, Suite 800

Wichita, KS 67202

NW SE NE, SEC. 24, T 17 S, R 30 W/E

3500 feet from N/S section line

1060 feet from W/E section line

Lease Name Burmeister Well # 'D' 1

County Lane 150.80

Well Total Depth 4640 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 7:30 am Day: 22 Month: November Year: 19 84

Plugging proposal received from Mr. Taylor

(company name) DNB (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2230' with 50 sx cement

2nd plug at 1000' with 50 sx cement

3rd plug at 310' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 am Day: 22 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement, 2nd plug at 1000' with 50 sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-84

INV. NO. 5767

Signed

(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: November 12 1984
month day year

API Number IS- 101-21,079-00-00

OPERATOR: License # 5238
Name Petroleum, Inc.
Address 300 W. Douglas, Suite 800
City/State/Zip Wichita, KS 67202
Contact Person Monte Chadd
Phone (316) 793-8471

NW SE NE Sec 24 Twp 17 S Rge 30 ☐ East
(location) ☒ West

3500 Ft North from Southeast Corner of Section
1060 Ft West from Southeast Corner of Section
Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5476
Name DNB Drilling, Inc. 316-687-5471
City/State 535 N. Oliver, Wichita, KS 67208

Nearest lease or unit boundary line 860 feet.
County Lane

Lease Name Burmeister 'D' Well# 1

Domestic well within 330 feet: ☐ yes ☒ no

Municipal well within one mile: ☐ yes ☒ no

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ Swd ☐ Infield ☐ Mud Rotary
Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

Depth to Bottom of fresh water 150 feet

Lowest usable water formation Dakota

Depth to Bottom of usable water 1200 feet

Surface pipe by Alternate: 1 ☐ 2 ☒

Surface pipe to be set 250 feet

Conductor pipe if any required 77 feet

Ground surface elevation feet MSL

This Authorization Expires 5-5-85

Approved By 11-5-84 R

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 4500 feet

Projected Formation at TD Mississippi

Expected Producing Formations

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

to 11-5-84 Signature of Operator or Agent

Jim A. Wilcox

Title District Landman

MHC/KOHE 11/5/84

Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1984

CONSERVATION DIVISION
Wichita, Kansas