

1060312

To:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Operator: Gear Petroleum Co., Inc.

Name &
 Address 300 Sutton Place
 Wichita, KS 67202

API NUMBER 15- 101-21,025 00-00

C E/2 SW, SEC. 25 ; T 17 S, R 30 W/
 1320 N SE Corner of
 feet from ~~XXX~~ section line
 3300 W SE Corner of
 feet from ~~XXX~~ section line

Lease Name Penka Well # 1-25

County Lane

Well Total Depth 4666 151.65 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 20 Month: August Year: 19 84

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1400' with 50 sx cement

3rd plug at 400' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by *Paul A. Luther*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 pm Day: 20 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 50 sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate ~~STATE CORPORATION COMMISSION~~ 15 sx cement.

AUG 24 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(if additional description is necessary, use BACK of this form.)

INVOICED

(xxx did not) observe this plugging.

DATE 8-29-84

INV. NO. 3433

8-20 OCT 02 1984

Signed *Paul A. Luther*
(TECHNICIAN)