

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21814-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 25-17S-30W  
790 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: DOWD Well Number: 1  
County: LANE Total Vertical Depth: 4635 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Surface Casing Size: 8.625 feet: 228 \$150.64

Well Type: DH UIC Docket No: Date/Time to Plug: 06/11/2003 9:00 PM  
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.  
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40-0' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 06/12/2003 12:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:  
1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40-0' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED  
JUN 13 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
JUN 12 2003  
KCC Dodge City

Signed Steve Durrant  
(TECHNICIAN)

INVOICED  
DATE 6-13-03  
INV. NO. 2003061641