

1120009

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 101-21,054 -00-00

SEC. 21, T 17 S, R 30 W
N SE Corner of
3300 FEET FROM ~~N/S~~ SECTION LINE
W SE Corner of
660 FEET FROM ~~W/S~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5181

LEASE NAME Magie 'A' WELL # 3

OPERATOR Donald C. Slawson & Pet., Inc.
NAME 200 Douglas Building
ADDRESS Wichita, KS 67202

COUNTY Lane

WELL TOTAL DEPTH 4645 150.96 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8 FEET 472

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D&A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Slawson Drilling Co., Inc. LICENSE NUMBER 5657

ADDRESS 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 9:00 pm DAY: 9 MONTH: October YEAR: 19 84

PLUGGING PROPOSAL RECIEVED FROM Glenn Conway

(COMPANY NAME) Slawson (PHONE) 316-263-3201

WERE: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2220' with 50 sx cement

2nd plug at 1500' with 80 sx cement

3rd plug at 525' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

PLUGGING PROPOSAL RECEIVED BY Don C. Uebel
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 10:15 pm DAY: 9 MONTH: October YEAR: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1500' with

80 sx cement, 3rd plug at 525' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat/hole with

15 sx cement.

STATE CORPORATION COMMISSION

OCT 12 1984

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Don C. Uebel
(TECHNICIAN)

INVOICED

DATE 10-15-84

INV. NO. 4320

10-9

FORM CP-2/3
REV. 6-83