

1 070838

8-13

API NUMBER 15-101-21,556 -00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NW, SEC. 28, T 17 S, R 30 (N/E)

2980 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name McGuire "C" Well # 1

Operator: Slawson Exploration Company, Inc.

County Lane McCue JDKr 150.09

Name & Address 104 S. Broadway, Suite 200

Well Total Depth 4618 feet

Wichita, KS 67202-4165

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 13 Month: 8 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2235-56'

1st plug at 2256' with 50 sx cement, 2nd plug at 1250' with 50 sx cement,

3rd plug at 625' with 50 sx cement, 4th plug at 395' with 50 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 13 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,

2nd plug at 1250' with 50 sx cement,

3rd plug at 625' with 50 sx cement,

4th plug at 395' with 50 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 15 1990

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (do not XXXXX) observe this plugging.

DATE: 8-23-90

INV. NO. 29027

Signed Dan Anderson (TECHNICIAN)

EFFECTIVE DATE: 8-5-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

15-101-21,556-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... August ... 1990 ...
month day year

SE SW NW Sec 28 Twp 17 S, Rg 30 East West

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 South Broadway, Suite 200
City/State/Zip: Wichita, Kansas, 67202-4165
Contact Person: Robert B. Jenkins
Phone: (316) 263-3201

2980' feet from South line of Section
4290' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC.

County: Lane
Lease Name: McCue "C" Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2872' GR. (Seis) feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 1200'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 350'
Length of Conductor pipe required: None
Projected Total Depth: 4600'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

Well Drilled For: Well Class: Type Equipment:

X Oil Inj Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWMO Disposal X Wildcat Cable
Seismic; # of Holes

If OWMO: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #: 17-400 well farm pond other
Will Cores Be Taken? yes X no
If yes, proposed zone:

Exp. 1/31/91

AFFIDAVIT

250' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101a

RECEIVED
STATE COMMISSION

Pusher Greg Davidson
SPUD DATE 8-4-90 1990 INIT. GB

LENGTH SURFACE PLANNED 350'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 363 CONDUCTOR
ANHYDRITE T- 2235 B- 2256 ELEVATION

TD 4618 FORMATION

RAN PIPE @ SX DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 2250 Ft. W/ SX
Anhydrite Base @ 2256 Ft. W/ 50 SX
1/2 Base Anyh. @ 1250 Ft. W/ 50 SX
1/2, 1/2 Plug @ 425 Ft. W/ 50 SX
Bottom Surface @ 395 Ft. W/ 50 SX
40' Plug @ 40-0 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX

WATER WELL SX (Irr. Well) Pond
Hauling

TECHNICIAN MS DATE 8-10-90

TYPE OF CEMENT 60/40 60% 1/4 Flocc

STARTING TIME 2:00 (AM/PM) DATE 8-13-90

COMPLETION TIME 3:45 (AM/PM) DATE

CEMENT COMPANY Allied

AUG 15 1990

CONSERVATION DIVISION
Wichita, Kansas