

1060357

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,051-00-00

SW NW NW, SEC. 28, T 17 S, R 30 W/RX
N SE Corner of
4290 feet from ~~XXX~~ section line
W SE Corner of
4950 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Williams 'BB' Well # 1

Operator: Donald C. Slawson

County Lane

Name & Address 200 Douglas Building

Well Total Depth 4663 ^{157.55} feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 5 Month: October Year: 19 84

Plugging proposal received from Jim Loftis

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1400' with 50 sx cement

3rd plug at 500' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 5 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 50

sx cement, 3rd plug at 500' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

INVOICED

(~~XXX~~ did not) observe this plugging.

DATE 10-15-84

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 4319

10-5