

1 050562

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15-101-20,171~~ 15-101-2017-0000

C SW NW, SEC. 36, T 18 S, R 28 (W)X
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5408

Lease Name Seifried Well # (SWD)

Operator: Moble C. Hoover

County Lane Lane 150.64

Name & Address NBC Plaza, Suite 302

Well Total Depth 4635 feet

El Dorado, AR 71730

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Edward C. Myers, Jr. for Moble C. Hoover License Number 5408

Address NBC Plaza, Suite 302, El Dorado, AR 71730

Company to plug at: Hour: 8:30 am Day: 1 Month: July Year: 19 85

Plugging proposal received from Edward C. Myers

(company name) Moble C. Hoover (phone) 501-863-4531

were: 4 1/2" at 2094' PBSD 1970' Perfs at 1750-1710 & 1630-1610 Plugged with casing in the hole. 4 1/2" was cemented from bottom to top. No recovery

Pumped 50 sx 50/50 Pozmix 2% gel 2% cc with 1/4 pound flowseal then pumped 150 sx 50/50 Pozmix 2% gel 3% cc.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:45 pm Day: 1 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Pumped 50 sx cement (50/50 Pozmix 2% gel 2% cc & 1/4 lb. flowseal) then pumped 150 sx cement (50/50 Pozmix 2% gel 3% cc)

RECEIVED
STATE CORPORATION COMMISSION

7-2-85 Cement fell to 150'. Pushed plug down ^{4 1/2"}_{8 5/8"} and pumped 5 sx cement to surface.

Maximum pressure 300 psi and shut in 100 psi

Remarks: No Recovery. Cemented by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did / did not) observe this plugging.

DATE 7-18-85

Signed Richard W. Lucy
(TECHNICIAN)

INV. NO. 9001