

To: 1 120593
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
2007 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.

Name:

Address 125 N. Market, Suite 1000

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒ X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 20 Month: 7 Year: 19 91

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling Company (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2074-2102'

1st plug at 2110' with 50 sx cement, 2nd plug at 1060' with 50 sx cement,

3rd plug at 530' with 50 sx cement, 4th plug at 240' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ☒ X

Operations Completed: Hour: 11:50 a.m. Day: 20 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2110' with 50 sx cement,

2nd plug at 1060' with 50 sx cement,

3rd plug at 530' with 50 sx cement,

4th plug at 240' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

(XXXX) did not observe this plugging.

INVOICED

DATE 8-8-91

INV. NO. 32609

Signed

(TECHNICIAN)

EFFECTIVE DATE: 3-14-91

15-101-21,577-00-00

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K. C. five (5) days prior to commencing well

Expected Spud Date 3 28 91
month day yearNW SE SW Sec 36 Twp 18 S, Rg 28 East
X WestOPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: 316/267-4375990' feet from South line of Section
3630' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)CONTRACTOR: License #: 5420
Name: White & Ellis Drilling Co.County: Lane
Lease Name: Estes Well #: 1
Field Name: WildcatIs this a Prorated Field? yes X no
Target Formation(s): Lansing/Kansas CityNearest lease or unit boundary: 990 ft.
Ground Surface Elevation: 2719 feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water: 75'

Depth to bottom of usable water: 1175'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 240'

Length of Conductor pipe required: None

Projected Total Depth: 4650'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:

... well ... farm pond X ... other

DWR Permit #: ...

Will Cores Be Taken? yes X no

If yes, proposed zone: ...

If OWO: old well information as follows:

Operator: ...

Well Name: ...

Comp. Date: ... Old Total Depth ...

Directional, Deviated or Horizontal well? no

If yes, total depth location: STATE CORPORATION COMMISSION

RECEIVED

Exp. 9/14/91

JUL 24 1991

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher: Bob Kasper
SPUD DATE 7-12-91 INIT. CK
LENGTH SURFACE PLANNED 240
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8" @ 219 CONDUCTOR
ANHYDRITE T-2014 B-2102 ELEVATION
TD 4635' FORMATION Miss.
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2110 Ft. W/ 50 SX
1/2 Base Anyh. @ 1060 Ft. W/ 50 SX
1/2, 1/2 Plug @ 530 Ft. W/ 50 SX
Bottom Surface @ 240 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN DR DATE 7-15-91
TYPE OF CEMENT 60-40-690 4 lbs. Seal.
STARTING TIME 9:30 (AM/PM) DATE 7-20-91
COMPLETION TIME 11:50 (AM/PM) DATE 7-20-91
CEMENT COMPANY Allied