

1052356

TO:
STATE CORPORATION COMMISSIONAPI NUMBER 15-101-21,773 -00-60
NE SE SE SEC. 34, T 18 S, R 28 WCONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HERNDON WELL # 1-34

TECHNICIAN'S PLUGGING REPORT

COUNTY LANEOPERATOR LICENSE # 30705WELL TOTAL DEPTH 4540 FEETOPERATOR: YOUNGER ENERGY COMPANY PRODUCTION CSG: SIZE " FEETNAME AND 453 S WEBB RD., SUITE 100 SURFACE CASING: SIZE 8 5/8" @ 204' WITH SXADDRESS WICHITA, KS 67207ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A XOTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR SHIELDS DRILLING LICENSE NUMBER 5184ADDRESS PO BOX 709 RUSSELL, KS 67665-0709COMPANY TO PLUG AT: HOUR: 5:00 AM DAY: 04 MONTH: 12 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM BURT BEERY(COMPANY NAME) SHIELDS DRILLING (PHONE) 785-483-3141WERE: 1ST PLUG AT 2050' WITH 50 SX CEMENT. 2ND PLUG AT 1230' WITH 80 SX CEMENT.3RD PLUG AT 630' WITH 40 SX CEMENT. 4TH PLUG AT 230' WITH 40 SX CEMENT.5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.PLUGGING PROPOSAL RECEIVED BY RICHARD LACEYPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE XOPERATIONS COMPLETED: HOUR: 8:15 AM DAY: 04 MONTH: 12 YEAR: 1999ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE1ST PLUG AT 2050' WITH 50 SX CEMENT. 2ND PLUG AT 1230' WITH 80 SX CEMENT.3RD PLUG AT 630' WITH 40 SX CEMENT. 4TH PLUG AT 230' WITH 40 SX CEMENT.5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.REMARKS: USED 160/40 POZMIX 6% GEL 1/4" FLO SEAL BY ALLIED.(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) DIVISION
WICHITA, KS.

I DID NOT OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

INV. NO.

061038

RECEIVED

KANSAS CORPORATION COMMISSION

DEC 13 1999

INVOICED

DATE

12/23/99