

To: 1 060680
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,231 - 00-00
Appx. W/2 NW SW SEC. 29, T 18 S, R 28 W/EX
2192 feet from S section line
4738 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9816

Lease Name Hineman Well # 1-29

Operator: Fagin Exploration Company

County Lane 152.43

Name & Address 1801 California Street, Suite 4380

Well Total Depth 4690 Mississippi feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 3 Month: October Year: 19 85

Plugging proposal received from Lloyd Dellett

(company name) Murfin (phone) 316-267-3241

Elevation 2714'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2100'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 am Day: 3 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2110' with 50 sx cement, 2nd plug at 1350' with 80
sx cement, 3rd plug at 330' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(If additional information is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION
(do not observe this plugging.)

DATE 10-15-85

OCT 10 1985

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 10568

CONSERVATION DIVISION
Wichita, Kansas