

1 100026

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION

130 S. Market, Room 2078

Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Operator: Landmark Energy Explor., Inc./

Name: Vess Oil Corporation

Address: 1861 N. Rock Rd., Ste. 205

Wichita, KS 67206

3-10

API NUMBER 15- 101-21,715 -00-00

50' E & 30' S of

NE SW SE, SEC. 27, T 18 S, R 28

960 feet from S section line

1600 feet from E section line

Lease Name Burmeister Well 1-27

County Lane

Well Total Depth 4620 150.15 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address: RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 10 Month: 3 Year: 1996

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1980-2010'

1st plug at 2010' with 50 sx cement, 2nd plug at 1280' with 80 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Gary Winters

(TECHNICIAN'S SIGNATURE)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6 p.m. Day: 10 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 2110' with 50 sx cement,

2nd plug at 1310' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 13 1996

INV. NO. 45038

Signed Gary Winters (TECHNICIAN)

EFFECTIVE DATE: 2-21-96DISTRICT 1
STATE Yes V ToState of Kansas 15-101-21,715-00-00
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPE

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date February 16 1996
month day yearSpot 50° E 130° S
NE SW SE 27 Twp 18 S. Rg 28 X East WestOPERATOR: License # 06113
Name: Landmark Energy Expl., Inc./Vess. Oil Corp.
Address: 1861 N. Rock Rd., Suite 205
City/State/Zip: Wichita, KS 67206
Contact Person: Jeff Wood
Phone: (316). 683-8080990 960 feet from South North line of Section
1650 1600 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR(NOTE: Locate well on the Section Plat on Reverse Side)
County: LaneLease Name: Burmeister Well #: 1-27Field Name: unnamedIs this a Propped/Spaced Field? yes X no
Target Formation(s): Lansing KC & MarmatonNearest lease or unit boundary: 990'Ground Surface Elevation: 2734 feet MSLWater well within one-quarter mile: yes X noPublic water supply well within one mile: yes X noDepth to bottom of fresh water: 180'Depth to bottom of usable water: 1840' - 1780'Surface Pipe by Alternate: 40' 1/2" X 2Length of Surface Pipe Planned to be set: 315'Length of Conductor pipe required: N/AProjected Total Depth: 4650'Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

well farm pond X other

DWR Permit #: _____

Will Cores Be Taken? yes X no

If yes, proposed zone: _____

200' Alt. II Req.

AFFIDAVIT

Exp. 8/16/96

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:RECEIVED
KANSAS CORP COMM
MAR 12 A 11:51

4520

Pusher Gred DavidsonSPUD DATE 3-1-96 INIT. SDLENGTH SURFACE PLANNED 375 335RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.RATHOLED AHEAD? Y N SIZE HOLESURFACE PIPE @ CONDUCTORANHYDRITE T- 1722 B- W ELEVATIONTD 4620 FORMATIONRAN PIPE @ SX DV TOOL SX ALT II DONE Y NArbuckle Plug @ Ft. W/ SXHug./Council @ 2110 Ft. W/ SXAnhydrite Base @ 2010 Ft. W/ 50 SX1300
1/2 Base Anyh. @ 1240 Ft. W/ 80 SX1700
1/2, 1/2 Plug @ 600 Ft. W/ 40 SX360
Bottom Surface @ 360 Ft. W/ 40 SX40
40' Plug @ 40 Ft. W/ 10 SXRAT HOLE CIRC/W 12 SX MOUSE HOLE W/ no SXWATER WELL no SX (Irr. Well Pond)TECHNICIAN G.W. DATE 3-08-96 HaulingTYPE OF CEMENT 604062-44-1016STARTING TIME 4:00 (AM/PM) DATE 3-10-96COMPLETION TIME 6:00 (AM/PM) DATE 3-10-96CEMENT COMPANY Milum