

1 060742

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,260-00-00

SE SW, SEC. 3, T 17 S, R 30 W/X

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Colvin Well # 1

Operator: Lebsack Oil Production, Inc.

County Lane

Name &

Address P. O. Box 489

Well Total Depth 4561 Mississippi 148,23 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:30 am Day: 11 Month: December Year: 19 85

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2233-2262' Elevation 2854' station

1st plug at 1800' with 80 sx cement

2nd plug at 1250' with 80 sx cement

3rd plug at 270' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5:45 pm Day: 11 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1778' with 60 sx cement. Tagged cement and put 20 sx

cement on top. 2nd plug at 1250' with 60 sx cement, 3rd plug at 270' with 40 sx cement,

4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Halliburton. Lost hole - circulation @ 1800'
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION

Signature Paul A. Luthi
(TECHNICIAN)

DATE DEC 20 1985

DEC 20 1985

INV. NO. 11678

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Collected
CARD MUST BE SIGNED
11-26-85

Starting Date: 11-26-85
month day year

API Number IS- 101-21,260-00-00

OPERATOR: License # 5210
Name Lebsack Oil Production, Inc.
Address Box 489
City/State/Zip Hays, Kansas 67601
Contact Person Wayne Lebsack
Phone 316-938-2396

K SE SE SW (location) Sec 3 Twp 17 S Rge 30 East West

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, Ks 67202

* 2970 330 Ft North from Southeast Corner of Section
Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet
County Lane
Lease Name Colvin Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: add well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4650 feet
Projected Formation at TD Mississippian
Expected Producing Formations Mississippian

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1150 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 250 feet
Conductor pipe if any required feet
Ground surface elevation 2854 feet MSI
This Authorization Expires 5-21-86
Approved By 11-21-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. *was SW SE SE 990 FEL*

11-25-85 Signature of Operator or Agent *Rex Curtis* Title Sec. Treas. Lebsack Oil Prod. Form C-1 4/84

252' of 8 3/8 on 12/2/85

wayne Stuebel

4501 - cherokee sd

SFL = 900'

Solid Blk
1850'

Fluid 1300

Solid Blk
40% - 5% b.c.

Down 1800'
no problem

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1985

CONSERVATION DIVISION
Wichita, Kansas