

1 050815

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,978 -00-00

SE NE NE, SEC. 2, T 17 S, R 30 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name 1st Baptist Well # 1

Operator: L. D. Drilling, Inc.

County Lane 150.64

Name & Address

Well Total Depth 4635 feet

R. R. 1, Box 183B

Conductor Pipe: Size feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor L. D. Drilling, Inc. License Number 6039

Address R. R. 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 29 Month: May Year: 19 86

Plugging proposal received from L. D. Davis

(company name) L. D. Drilling (phone) 316-793-3051

were: 5 1/2" at 4632' Perfs at 4532-4537' Alternate 2 cementing procedures done 6-85

5 1/2" cemented from 1350' to surface

Squeeze well with 3 sx hulls and 175 sx cement

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 am Day: 29 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Pumped down 5 1/2" with 3 sx hulls and 150 sx cement (2 sx hulls mixed with cement).

Maximum pressure 2600 psi and shut in 2000 psi

Remarks: No recovery. Used Econolite by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

JUN 3 1986

DATE

INV. NO. 14035

Signed Richard M. Lutz
(TECHNICIAN)FORM CP-2/3
Rev. 01-84RECEIVED
STATE CORPORATION COMMISSION
JUN 02 1986
CONSERVATION DIVISION
Wichita, Kansas