

1 060837

API NUMBER 15- 101-21,299 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NE, SEC. 1, T 17 S, R 30 W EX
4320 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Jennison 'L' Well # 1

Operator: Donald C. Slawson

County Lane 149.34

Name & Address 200 Douglas Building

Well Total Depth 4595 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 6:30 pm Day: 15 Month: March Year: 19 86

Plugging proposal received from Jack Richardson

(company name) Slawson (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2240-2269'
Elevation 2842' KB

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 75 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:45 pm Day: 15 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2269' with 50 sx cement, 2nd plug at 1443' with 75 sx

cement, 3rd plug at 369' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. CONSERVATION DIVISION
(if additional description is necessary, use BACK of this for Wichita, Kansas)

INVOICED

DATE MAR 20 1986

INV. NO. 13037

3-15

Signed Paul A. Luthi
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 7 1986

API Number 15- 101-21,299-00-00

OPERATOR: License # 5181 Name SLAWSON, DONALD C. Address 200 Douglas Building City/State/Zip Wichita, Kansas 67202 Contact Person Bill Horigan Phone (316) 263-3201

SW NW NE Sec 1 Twp 17 S, Rg 30 East West 4320' 2310' Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 5657 Name Slawson Drilling Co. City/State Great Bend, Kansas

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330' feet County Lane

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Jennison 'H' Well # 1 Ground surface elevation 2838' GR. SUR. feet MSL Domestic well within 330 feet: Municipal well within one mile: Depth to bottom of fresh water 190' Depth to bottom of usable water 1150' Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 320' Conductor pipe required Projected Total Depth 4600' feet Formation Mississippian

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 3/6/86 Signature of Operator or Agent Robert B. Jenkins Title Western Kansas District Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt 1 2 This Authorization Expires 3-6-86 Approved By 3-6-86

Move in 3-7-86 320' 8 1/2" 100

SW NW NE Sec 1 Twp 17 S, Rg 30 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2280' base up feet depth with 50 sxs of 60/40 poz w/6% Gel
2nd plug @ 1320' base chg feet depth with 75 sxs of 60/40 poz w/6% Gel
3rd plug @ 360' feet depth with 40 sxs of 60/40 poz w/6% Gel
4th plug @ 40' feet depth with 10 sxs of 60/40 poz w/6% Gel
5th plug @ feet depth with sxs of
(2) Rathole with 1.5 sxs (b) Mousehole with sxs

PUSHER Jacob Richardson

TD 45.95 FORMATION Mix

SURFACE PIPE 8 5/8" @ 339

ANHYDRITE 2240 ELEVATION 2842.15

STARTING TIME & DATE 3-15-86 6:30 PM

COMPLETION TIME & DATE 3-15-86 10:45 PM

1st PLUG @ 2269 FT. W/ 50 SX

2nd PLUG @ 1443 FT. W/ 75 SX

3rd PLUG @ 369 FT. W/ 40 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ SX

CEMENT COMPANY Hall pump

TECHNICIAN Luthi

RECEIVED STATE CORPORATION COMMISSION MAR 20 1986 CONSERVATION DIVISION Wichita, Kansas