

1 030574

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,245 -00-00

App. N/2 NE NE SEC. 16, T 17 S, R 30 W

4950 feet from S section line
540 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Schadel 'P' Well # 2

Operator: Slawson, Donald C.

County Lane 149.83

Name &

Address 200 Douglas Building

Well Total Depth 4610 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 19 Month: November Year: 19 85

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

Elevation 2869

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2250

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 am Day: 19 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement, 2nd plug at 1320' with 80

sx cement, 3rd plug at 510' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED
NOV 26 1985

RECEIVED
STATE CORPORATION COMMISSION

DATE

IN.V. NO. 11238

11-19

NOV 20 1985

Signed Steve Durrant (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL The prod. csg. will be cmted (see rules on reverse side) from below useable water to surf. immediately upon compl. of well.

Starting Date October 31, 1985 month day year 3-24

API Number 15- 101-21,245-00-00

OPERATOR: License # 5181 Name SLAWSON, DONALD C. Address 200 Douglas Bldg. City/State/Zip Wichita, Kansas 67202 Contact Person Bill Horigan Phone 316.263-3201

APP N/2 NE NE Sec. 16 Twp. 17 S, Rg. 30 West 4950' 540' Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5657 Name Slawson Drilling Co. City/State Wichita, Kansas

Nearest lease or unit boundary line 330' feet County Lane Lease Name Schadel 'P' Well # 2 Ground surface elevation 2869 GR feet MSL

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildeat Cable

Domestic well within 330 feet: yes no Municipal well within one mile: yes no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 190' Depth to bottom of usable water 1150' Surface pipe planned to be set 440' Projected Total Depth 4600' feet Formation Mississippi

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 10-30-85 Signature of Operator or Agent Robert B. Jenkins Title Geologist Western District

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2 This Authorization Expires 4-30-86 Approved By 10-30-85

8 3/8 - 440 + Speed 11-8-85

PUSHER J. L. Conway TD 4610 FORMATION M155 SURFACE PIPE 8 3/8 @ 472 ANHYDRITE 2869 ELEVATION 2869 STARTING TIME & DATE COMPLETION TIME & DATE 9:45 am / 11/19/85 1st PLUG @ 30' @ 50 FT. W/ 50 SX 2280 2nd PLUG @ 30' @ 80 FT. W/ 80 SX 1320 3rd PLUG @ 30' @ 110 FT. W/ 140 SX 910 4th PLUG @ 50' @ 140 FT. W/ 110 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ Hand - SX CEMENT COMPANY Halliburton TECHNICIAN Steve Durrant

RECEIVED STATE CORPORATION COMMISSION NOV 20 1985 CONSERVATION DIVISION Wichita, Kansas