

1 050593

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,836-0008  
40' S & 150'E of SW NW SE, SEC. 19, T 17 S, R 22 W/X

1610 feet from S section line

2160 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Irma Pomije Well # 1

Operator: A. Scott Ritchie

County Ness <sup>142.68</sup>  
(Mississippi)

Name & Address 125 North Market, Suite 950

Well Total Depth 4390 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 3 Month: August Year: 1985

Plugging proposal received from Mort Sherfick

(company name) Murfin (phone) 316-267-3241

Elevation 2332'  
Anhydrite 1605'

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1612' with 50 sx cement

2nd plug at 860' with 80 sx cement plug 1 sack floeal

3rd plug at 340' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:15 am Day: 3 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1612' with 50 sx cement, 2nd plug at 860' with 80 sx cement and 1 sack floeal, 3rd plug at 340' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-14-85

INV. NO. 9593

8-3

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1985

Signed Richard W. Lacey  
(TECHNICIAN)