

1 060801

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,002-6000
50' N & 155' E (Irregular section)
SW NE NW, SEC. 19, T 17 S, R 22 W/XX
4340 feet from S section line
3475 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name George Brown Well # 1

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

County Ness 142.35
Well Total Depth 4380 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11:45 am Day: 11 Month: February Year: 19 86

Plugging proposal received from Mort Sherfick

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1632-1669'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:15 pm Day: 11 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 1020' with 80 sx
cement, 3rd plug at 270' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION

FFB 17 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this report)

INVOICED (Do not) observe this plugging.

DATE 1-17-86

REV. NO. 12635

2-11

Signed Paul A. Luthi
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

2

Starting Date 1 29 86 month day year

API Number 15- 135-23,002-0000
50' N & 155' E *Irregular Section*
of SW. NE. NW Sec. 19. Twp. 17. S. Rg. 22. X West
4340 Ft. from South Line of Section
3475 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

OPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Leah Ann Kasten
Phone (316) 267-4375

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, Kansas

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Nearest lease or unit boundary line 835 feet
County Ness
Lease Name George Brown Well # 1
Ground surface elevation est. 2358 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 100'
Depth to bottom of usable water 700'
Surface pipe planned to be set 240'
Projected Total Depth 4450'
Formation Mississippi

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing.
Date 1/27/86 Signature of Operator or Agent Leah Ann Kasten Title Geologist

For KCC Use:
Conductor Pipe Required feet: Minimum Surface Pipe Required 200 feet per AN X
This Authorization Expires 7-23-86 Approved By 1-23-86

move in 2-4-86 set 240' of 8 1/2"

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug #, Depth (ft), Cement (sxs), and Notes. Includes entries for 1st through 5th plugs and a rat hole.

PUSHER Mort Shirkley
TD 4380 FORMATION MISS
SURFACE PIPE 8 7/8 @ 251
ANHYDRITE 1632 ELEVATION 2342
STARTING TIME & DATE 11:46 AM 2-11-86
COMPLETION TIME & DATE 2:16 PM 2-11-86
1st PLUG @ 1650 FT. W/ 50 SX
2nd PLUG @ 1020 FT. W/ 80 SX
3rd PLUG @ 270 FT. W/ 40 SX
4th PLUG @ 50 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX

CEMENT COMPANY Alced Plugged by
TECHNICIAN South's saw all

Brourne
2 1/2
55
3/4
RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1986
CONSERVATION DIVISION
Wichita, Kansas