

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24142-00-00
Spot: NWNE Sec/Twnshp/Rge: 26-17S-22W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: SUN TERRA Well Number: 1
County: NESS Total Vertical Depth: 4253 feet

Operator License No.: 31430
Op Name: WHITE EAGLE RESOURCES CORP.
Address: 881 W. CHESTNUT CIRCLE
LOUISVILLE, CO 80027

Conductor Pipe: Size feet: 8/38.22
Surface Casing: Size 8.625 feet: 221 WITH 150 SX CMT
Production: Size 5.5 feet: 4232 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/25/2001 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND BACK TO 4180' WITH 5 SX CMT ON TOP BY DUMP BAILER. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 950' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE
Date/Time Plugging Completed: 09/25/2001 9:00 AM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE @ 4233-53'. SANDED TO 4187' & 5 SX CMT. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 950' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED. RECOVERED 3247' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael J. Maier
(TECHNICIAN)

RECEIVED

OCT 04 2001

KCC WICHITA

INVOICE L'SEP 27 2001

DATE 10-4-01

INV. NO. 2002060734 MP

FORM CP-23