

To: 1 060032
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 135-23,949-0000
C SE SW, SEC. 12, T 17 S, R 22 W/X
660 feet from S section line
3300 feet from E section line

Operator License / 31319
Operator: Plainsco, Ltd.
Name & Address: 1776 Lincoln St., Ste. 1314
Denver, CO 80203

Lease Name Thompson Well / 12-14
County Ness 143.33
Well Total Depth 4410 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 1:20 p.m. Day: 8 Month: 5 Year: 1997

Plugging proposal received from David Norby
(company name) Plainsco, Ltd. (phone) 303-832-6135

Work: 5 1/2" at 4410' w/125 sx cement, PBSD 4235', Perfs at 4145-57', DV tool at 1600'-no cement
1st plug set CIBP at 4100' with 2 sx cement on top,
2nd plug at 1640' with 50 sx cement,
3rd plug at 850' with 80 sx cement,
4th plug at 230' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 8 Month: 5 Year: 1997

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4135' with 5 sx cement on top,
2nd plug perforated at 850', circulated with 200 sx cement.
Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(I should observe this plugging.)

DATE MAY 15 1997

INV. NO. 48125

5-8 JUL 11 1997

Signed Michael J. Mason
(TECHNICIAN)

KANSAS RECEIVED COPY
MAY 14 4 11:15