

1 090353

22673.00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22-073

~~NW SE NW~~ SEC. 13, T 17 S, R 22 W ~~XX~~

3800 feet from S section line

3800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9692

Lease Name Alberts Well # 1

Operator: Nesco Inc.

County NESS 139.36

Name & Address Box 177

Well Total Depth 4288 (Miss) feet

Bazine, Kans. 67516

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 314

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co., Inc. License Number none

Address N. Hwy 283, Ness City, KS 67560

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: May Year: 1985

Plugging proposal received from Ed Leiker

(company name) Edward P. Leiker (phone) 913-625-5310

were: 4 1/2" set at 4287; Perforations at 4284-86; recover pipe and plug well by pumping 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and release a 4 1/2" plug. Finish with 125sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 11:45am Day: 16 Month: May Year: 1985

ACTUAL PLUGGING REPORT Set Cast iron bridge plug at 4130 and sanded to 4000' and put

2 sx cement on top of sand with bailer. Recovered 1550' of 4 1/2". Mounted plug

retaining swedge and mixed and pumped 3 sx hulls, 15 sx gel, 25 sx cement, 10 sx gel,

RECEIVED
STATE CORPORATION COMMISSION

1 sx hulls and release 4 1/2" wiper plug; then finished with 150 sx cement.

JUN 17 1985

Maximum pump pressure was 1000 lbs and shut in pressure was 200 lbs.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix with 2% gel, 3% CaCl; cementing by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

JUN 25 1985

Signed Robert Barkhutton
(TECHNICIAN)

DATE 6-19-85

INV. NO. 8600 5-16