

1 060202

12-1

API NUMBER 15- 093-21,305 0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 SE NE, SEC. 17, T 21 S, R 35 W
2970 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5003

Lease Name Eatinger "A" Well / 1-17

Operator: McCoy Petroleum Corporation

County Kearny

Name & Address
110 S. Main, Ste. 500
Wichita, KS 67202

Well Total Depth 4980 161.85 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 110 S. Main, Ste. 500, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 1 Month: 12 Year: 19 93

Plugging proposal received from Eugene Saloga

(Company name) Sweetman Drilling, Inc. (phone) 316-265-9697

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2200'

1st plug at 3200' with 100 sx cement, 2nd plug at 2250' with 50 sx cement,

3rd plug at 1100' with 50 sx cement, 4th plug at 700' with 40 sx cement,

5th plug at 410' with 50 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 a.m. Day: 1 Month: 12 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,

2nd plug at 2250' with 50 sx cement, 3rd plug at 1100' with 50 sx cement,

4th plug at 700' with 40 sx cement, 5th plug at 410' with 50 sx cement,

6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

Additional description is necessary, use BACK of this form.)

Observed this plugging. Signed _____ (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 02 1993
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE DEC 14 1993
INV. NO. 39514

FOR ALL USE
EFFECTIVE DATE: 11-17-93
DISTRICT: 1
SCAT: Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 093-21,305
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Nov 20 1993
month day year

Spot 572 SE NE Sec 17 Twp 21 S. Rg 35 East West

OPERATOR: License # 5003
Name: McCoy Petroleum Corporation
Address: 110 S. Main, Suite 500
City/State/Zip: Wichita, KS 67202
Contact Person: Robert O'Dell
Phone: (316) 265-9697

2970 feet from South / North line of Section
660 feet from East / West line of Section
IS SECTION REGULAR IRREGULAR
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5658
Name: Sweetman Drilling, Inc.

County: Kearny
Lease Name: Eatinger "A" Well #: 1-17
Field Name: Beymer North

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
 Gas ... Storage Pool Ext. ... Air Rotary
 OWD ... Disposal ... Wildcat ... Cable
 Seismic: # of Holes ... Other
 Other

Is this a Prorated/Spec'd Field? ... yes no
Target Formation(s): Marmaton
Nearest Lease or unit boundary: 330'
Ground Surface Elevation: 3150 Est. feet MSL

If OWD: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Water well within one-quarter mile: ... yes no
Public water supply well within one mile: ... yes no
* Depth to bottom of fresh water: 90'
* Depth to bottom of usable water: 1000'

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 400' +/-
Length of Conductor pipe required: -0-
Projected Total Depth: 5000'
Formation at Total Depth: Mississippian

Water Source for Drilling Operations:
 well ... farm pond ... other
DW Permit #: To be applied for
Vill Cores Be Taken?: ... yes no
If yes, proposed zone: _____

AFFIDAVIT

Exp. 5/12/94
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well shall conform with the provisions of the Kansas Conservation Commission Act, Chapter 75, Article 27, Sections 101, et. seq.
It is agreed that the following minimum requirements will be met:

* Depths given by Chris Bean
200' Alt. II Req.

RECEIVED RECEIVED
STATE CORPORATION COMMISSION
KANSAS CORPORATION COMMISSION
DEC 02 1993

Pusher Eyene Sologu
SPUD DATE 11-22-93 INIT. ES/SJ
LENGTH SURFACE PLANNED 381 LINED
RESERVE PIT STATUS- REMOVE FLUID 381 when done bbbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 381 CONDUCTOR
ANHYDRITE T- 2200 B-
TD 4480 FORMATION Mississippi
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ 3200 Ft. W/ 100 SX
Anhydrite Base @ 2250 Ft. W/ 50 SX
1/2 Base Anyh. @ 1100 Ft. W/ 50 SX
1/2, 1/2 Plug @ 700 Ft. W/ 40 SX
Bottom Surface @ 410 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL _____ SX (Irr. Well _____ Pond _____
Hauling _____
TECHNICIAN CM DATE 11-30-93
TYPE OF CEMENT 60/40 620 1/4 # ES
STARTING TIME 4:00 (AM/PM) DATE 12-1-93
COMPLETION TIME 8:30 (AM/PM) DATE 12-1-93
CEMENT COMPANY Halliburton

CONSERVATION DIVISION
Wichita, Kansas