

To: 061151  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-21-88  
API NUMBER 15-135-21,672-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

NW SE SW, SEC. 27, T 16 S, R 25 W/E  
990 feet from S section line  
3630 feet from E section line

Operator: Palomino Petroleum  
Name & Address: Route 5, Box STATE CORPORATION COMMISSION  
Newton, KS 67114  
RECEIVED  
10-25-88  
OCT 25 1988

Lease Name Dodrill Well # 1  
County Ness 145.28  
Well Total Depth 4477 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
CONSERVATION DIVISION  
Wichita, Kansas

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 21 Month: 10 Year: 19 88

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4466' Open Hole Elevation 2514' GL

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10: sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:25 p.m. Day: 21 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx  
cement.

Maximum pressure 700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2506' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Paul A. Luthie  
(TECHNICIAN)

DATE 10-28-88

INV. NO. 22839