

1 060995

KCC
941-00-00 TMB

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22, 194

SW NW NE, SEC. 35, T 16 S, R 25 W X

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4571

Lease Name Horacek Well # 1

Operator: Volga Oil Inc.

County Ness 141.38

Name & Address Box 278

Well Total Depth 4350 feet

Victoria, KS 67671

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 4:45 p.m. Day: 21 Month: 8 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4490' PRTD 4350' Open hole

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 21 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 130 sx cement.

Maximum pressure 700 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1430' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Do not observe this plugging.

DATE 8-25-87

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 17957

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1987
CONSERVATION DIVISION
Wichita, Kansas