

1 060788

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,278 -00-00

N/2 NW SE, SEC. 3, T 17 S, R 27 (W/B)

2310 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation.

Name &

Address 155 North Market, Suite 1000

Wichita, KS 67202

Lease Name Bowles "B" Well # 1

County Lane 136.57

Well Total Depth 4202 Lancing feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 27 Month: January Year: 19 86

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-269-7600

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2080' Elevation 2674'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 27 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2125' with 50 sx cement, 2nd plug at 1100' with 80 sx

cement, 3rd plug at 405' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JAN 30 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied. CONSERVATION DIVISION (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE JAN 31 1986

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 12221

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 15 86
month day year

API Number 15- 101-21,278-00-00
yes
N/2 NW SE Sec 3 Twp. 17 S, Rg. 27 East
2310 West
1980 Ft. from South Line of Section
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

OPERATOR: License # 5171
Name TXO Production Corp.
Address 155 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Jerry W. Collins
Phone 316-269-7600

Nearest lease or unit boundary line 330 feet

County Lane

Lease Name BOWLES "B" Well # 1

Ground surface elevation TBD feet MSL

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Surface pipe by Alternate: 1 2

Depth to bottom of fresh water 100

Depth to bottom of usable water 600 1000

Surface pipe planned to be set 350

Projected Total Depth 4650 feet

Formation Mississippi

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS 67202

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

_____ cementing will be done immediately upon setting production casing. 2 c/c/kate
Date 1-9-86 Signature of Operator or Agent Jerry W. Collins Title Drig. & Completion Engr.

For KCC Use:

Conductor Pipe Required _____ feet; Minimum Surface Pipe Required 250 feet per Alt. 2

This Authorization Expires 2-12-86 Approved By 1-10-86

move 1-21-86 350' of 8 5/8"

RECEIVED

STATE CORPORATION COMMISSION

JAN 30 1986

CONSERVATION DIVISION

D+A

PUSHER Allen Dick w/ TXO

TD 4202' FORMATION Lancing

SURFACE PIPE 3 7/8" @ 361'

ANHYDRITE 2080' ELEVATION 2674'

STARTING TIME & DATE _____

COMPLETION TIME & DATE 7:30 PM 1-27-86

1st PLUG @ 2125 FT. W/ 50 SX

2nd PLUG @ 1160 FT. W/ 80 SX

3rd PLUG @ 405 FT. W/ 50 SX

4th PLUG @ 40 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 10 SX

WATER WELL PLUGGED W/ _____ SX

CEMENT COMPANY Allied

TECHNICIAN D.G.

set 3
1st casing 30
2nd had clay 80
3rd 30' but they 00
4th 40' 08 3/10
15' rat 10 mouse
60/40 w/ 6% gel