

To: 1 080079
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-20,306 -00-00
NE NW, SEC. 3, T 17 S, R 27 W/8
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5285

Lease Name Bowles A Well / 1

Operator: The Dane G. Hansen Trust

County Lane 150.15

Name & Address P.O. Box 187

Well Total Depth 4620 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing, Co., Inc. License Number

Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 10:30 a.m. Day: 1 Month: 11 Year: 19 96

Plugging proposal received from Richard Wallgren

(company name) The Dane G. Hansen Trust (phone) 913-689-4816

were: 4 1/2" at 4295' w/150 sx cement, Perfs at 4041-44'

1st plug pump 2 sx hulls and 25 sx cement,

2nd plug perforate at 1250' and pump 165 sx cement,

3rd plug pump 150 sx cement down backside.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 1 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement, displaced to 3090'.

Maximum pressure 1000 psi and shut in 100 psi.

2nd plug perforated at 1250' and pumped 165 sx cement. Maximum pressure 700 psi and shut in 100 psi.

3rd plug pumped down 8 5/8" X 4 1/2" with 150 sx cement. Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED (and appropriate) observe this plugging.

Signed Kevin D Strube (TECHNICIAN)

DATE NOV 13 1996

INV. NO. 46948