

12-19

1 070772

API NUMBER 15- 101-21,536 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S/2 S/2 NW, SEC. 3, T. 17 S, R. 27 W/E

2970 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Bowles "A" Well # 6

Operator: The Dane G. Hansen Trust  
Name & Address P.O. Box 187  
Logan, KS 67646

County Lane 138.45

Well Total Depth 4260 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783

Address 340 Broadway Plaza, 105 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 2:30 p.m. Day: 19 Month: 12 Year: 19 89

Plugging proposal received from Carl McGuire

(company name) Galloway Drilling Company, Inc. (phone) 316-263-1793  
Elevation 2661'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2066-2102'

- 1st plug at 2100' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,
- 3rd plug at 340' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 p.m. Day: 19 Month: 12 Year: 19 89

- ACTUAL PLUGGING REPORT
- 1st plug at 2100' with 50 sx cement,
  - 2nd plug at 1300' with 80 sx cement,
  - 3rd plug at 340' with 40 sx cement,
  - 4th plug at 40' with 10 sx cement,
  - 5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(old) observe this plugging.

DATE 1-5-90

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 26800

EFFECTIVE DATE: 12-11-89

State of Kansas 101-21,536-00-002

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date December 10, 1989  
month day year

S/2 S/2 NW Sec 3 Twp 17 S, Rg 27 East  
 West

OPERATOR: License # 5285  
Name: The Dane G. Hansen Trust  
Address: P. O. Box 187  
City/State/Zip: Logan, Kansas 67646  
Contact Person: Dane G. Bales  
Phone: 913-689-4816

2970 feet from South line of Section  
3960 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5783  
Name: Galloway Drilling Co., Inc.

County: Lane  
Lease Name: Bowles 'A' Well #: 6  
Field Name: Pendennis South  
Is this a Prorated Field? yes X no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: N.A. feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 1100' / 1150'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 300'  
Length of Conductor pipe required: None  
Projected Total Depth: 4500  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations: Contractors Decision  
well farm pond other

Well Drilled For: Well Class: Type Equipment:  
X. Oil ... Inj ... Infield ... Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken? yes X no  
If yes, proposed zone: \_\_\_\_\_  
200' Alt. II Req.

Exp, 6/6/90

Set 300' of 8 5/8 on 12-11-89

AFFIDAVIT

PUSHER Carl McCann  
Daly & Hunt 4182  
TD \_\_\_\_\_ FORMATION \_\_\_\_\_  
SURFACE PIPE 8 5/8" @ 311  
2066 ELEVATION \_\_\_\_\_  
ANHYDRITE 2102  
STARTING TIME & DATE \_\_\_\_\_  
COMPLETION TIME & DATE \_\_\_\_\_  
1st PLUG @ 2100 FT. W/ 50 SX  
2nd PLUG @ 1300 FT. W/ 80 SX  
3rd PLUG @ 340 FT. W/ 40 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ \_\_\_\_\_ SX  
WATER WELL PLUGGED W/ \_\_\_\_\_ SX  
CEMENT COMPANY \_\_\_\_\_  
TECHNICIAN S.P.  
TYPE OF CEMENT 60/40/6 70

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1989  
CONSERVATION DIVISION  
Wichita, Kansas

5280	1650
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.