

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,941-00-00

C NW/4, Sec. 3, T 17 S, R 27 W/X

1320 feet from N/X section line

1320 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5288

Lease Name Bowles 'A' Well # 5

Operator: The Dane G. Hansen Trust
Name & P. O. Box 187
Address Logan, KS 67646

County Lane

Well Total Depth 4280 feet 139.10

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Co., Inc. License Number 5783

Address 340 Broadway Plaza Building, 105 S. Broadway, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 15 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Lloyd Warren

(company name) Galloway Drilling (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2070' with 50 sx cement

2nd plug at 1200' with 50 sx cement

3rd plug at 720' with 50 sx cement

4th plug at 360' with 40 sx cement

solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Signed Steve Stewart (TECHNICIAN)

7th plug to circulate rathole with 10 sx cement

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 am Day: 15 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement, 2nd plug at 1200'

with 50 sx cement, 3rd plug at 720' with 50 sx cement, 4th plug at 360' with 40

sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement, 7th plug to circulate rathole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 3-23-84
INV. NO. 0903
3-15

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Stewart (TECHNICIAN)