

1 060771

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,008 -00-00

NW SW NE, SEC. 1, T 17 S, R 27 W/EX

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Hagens G Well # 1

Operator: Thunderbird Drilling, Inc.  
Name:

County Lane 152.43

Address P. O. Box 18407  
Wichita, KS 67207-67218

Well Total Depth 4690' feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 8 Month: January Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4584' PBTB 4545' Perfs at 4148-58'; 3974-78'; 3954-60'

1st plug sand back to 3900' and dump 5 sx cement on top of sand through bailer

2nd plug shoot pipe at 1760' and pump 250 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:15 pm Day: 17 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 5 sx cement on top of sand through bailer, 2nd plug (1-8-86) shot pipe at 1760' and pumped 250 sx cement. Well went on vacuum at 4 bbls per min. Ran wire line (1-9-86) cement top at 772'.

(1-17-86) Ran wire line shot can to 696' and set off charge. Pumped 100 sx cement and 2 sx hulls.

STATE CORPORATION COMMISSION

JAN 27 1986

Maximum pressure 600 psi and shut in 350 psi

CONSERVATION DIVISION

Remarks: No recovery. Used 60/40 Pozmix 6% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

JAN 30 1986

Signed Paul A. Luthi  
(TECHNICIAN)

DATE

INV. NO. 12195