

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20018-00-00⁰¹
Spot: CW2SENE Sec/Twnshp/Rge: 5-17S-27W
3300 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MILLER N Well Number: 2
County: LANE Total Vertical Depth: 4745 feet

Operator License No.: 31627

Conductor Pipe: Size feet:

Operator Name: WHITETAIL CRUDE, INC

Surface Casing: Size 8.625 feet: 282

Address: 201 W ASH
NESS, KS 67560

Production: Size 5.5 feet: 4560 WITH 150 SX CMT

Liner: Size feet:

154.21

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/30/2000 2:40 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: MIKE FRITZLER

Company: WHITE TAIL CRUDE

Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 3875' WITH 2 SX CMT ON TOP. PERFORATE AT 1200' AND PUMP 155 SX CMT. PUMP 175 SX CMT ON BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/30/2000 3:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 3949-3954'. SANDED TO 3875' WITH 2 SX CMT ON TOP. HUNTED FOR HOLES AND FOUND THEM AT 1540'. PERFORATED AT 1200' AND PUMPED 155 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN WITH 300#. TIED ONTO BACKSIDE AND PUMPED 175 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN WITH 100#.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier
RECEIVED STATE CORPORATION COMMISSION (TECHNICIAN)

DEC 7 2000

INVOICED
DATE 12/1/00 DEC. 06 2000

CONSERVATION DIVISION
Wichita, Kansas

WVZ NO. 0001061141

Form CP-2/3