

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20017-00-00
Spot: CSENE Sec/Twnshp/Rge: 5-17S-27W
990 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: MILLER N Well Number: 1
County: LANE Total Vertical Depth: 4680 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet: 8/52.10
Surface Casing: Size 8.625 feet: 275
Production: Size 4.5 feet: 4280 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/21/2001 12:00 PM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: MIKE J. FRITZLER Company: FRITZLER TRUCKING Phone: (785) 798-3641

Proposed Plugging Method: SAND OFF CASING TO 3900', CAP WITH 4WX USING DUMP BAILER. SHOOT OFF 4-1/2 @ 1300' & PUMP 80 SX @ 1300'. PULL PUPE TO 720', PUMP 50 SX PLUG. PULL PIPE TO 300' & PUMP 40 SX PLUG 40 SX PLUG, PULL PIPE OUT & TOP OFF 8-5/8 WITH 10 SX.

Plugging Proposal Received By:

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/21/2001 6:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 4205-08 & 4214-17'. LEFT 4 JOINTS AND PACKER IN HOLE. SANDED BACK TO 3914' WITH 4 SX CMT ON TOP. CEDAR HILL LEAKING IN CASING AT 1700'. RUN TUBING IN HOLE WITH PACKER. TESTED CASING FROM 1400' TO 0' TO 300#. RUN TUBING IN HOLE TO 1700'. PUMPED 400# HULLS & 25 SX CMT WITH CC MIXED INTO CMT. PULLED TUBING OUT OF HOLE. LOADED 4 1/2" CASING & CASING WOULDN'T PRESSURE UP. SET CIBP @ 1402'. PERFORATED AT 1300'. PUMPED DOWN 4 1/2" 1/2 BPM AT 800#. STARTED DOWN HOLE WITH CMT. PUMP 130 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 600#. SQUEEZE OUT 60 SX CMT. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 175 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN AT 200#.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Kevin D Strube

RECEIVED

NOV 29 2001

NCC WICHITA

INVOICED

DATE 11-30-01

NV NO. 2002061001

(TECHNICIAN)

NOV 26 2001

MP

[Signature]
FORM CP-2/3