

1 070190

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,225-00-00
NW SW NW, SEC. 4, T. 17 S, R. 27 (W/P)
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285
Operator: Dane G. Hansen Trust
Name & Address P. O. Box 187
Logan, KS 67646

Lease Name Bowles Well # 1
County Lane 149.66
Well Total Depth 4605 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 11 Month: June Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4341' Perfs at 4052-54'; 4045-48'; 4211-13'; 4201-04'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer

2nd plug pump 70 sx cement down 4 1/2" and shut in

3rd plug pump 80 sx ^{down} 8 5/8" and shut in.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 11 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top of

sand through bailer, 2nd plug pumped 70 sx Allied ATL cement down 4 1/2" - Maximum

pressure 1000 psi and shut in 300 psi. Pumped 80 sx ATL down 8 5/8" - Maximum

pressure 100 psi and shut in 50 psi

Cement wt. 11.5 used 62 bbls of water.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1986

Remarks: No recovery. Used Allied ATL cement

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 18 1986

INV. NO. 14134

6-11

Signed Dan Goodrow
(TECHNICIAN)