

15-093-20406-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kearny County, Sec. 21 Twp. 21S Rge. 35 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW/4

Lease Owner Gas Producing Interprise
Lease Name Ely Well No. 2

Office Address Box 1332, Amarillo, Texas 79189

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 7-16 1977

Application for plugging filed 4-10 1978

Application for plugging approved 4-14 1978

Plugging commenced 5-20 1978

Plugging completed 5-22 1978

Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Krider Depth to top 2676 Bottom 2688 Total Depth of Well 3150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	Dolo & Anhy	2640	2676	8 5/8	510	None
Krider	Dolo	2676	2732	4 1/2	3125	2220
Winfield	Dolo & SD	2732	2786			
Council Grove	Limestone	2956	3126			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 10 sks. of cement from 2688 to 2550
Pump 35 sks. of cement from 400 to 300
Put 10 sks. of cement from 40 to 0

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Ser. Box 506 Liberal, Kansas 67901 No. 511


STATE OF Texas COUNTY OF Pottawatomie, ss.
(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of June, 1978



My commission expires July 19, 1979

Notary Public.

15-093-20406-0005 4

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Ely #2
C-NW Sec 21-21S-35W
Kearny County Kansas

Commenced: 4-19-77

Completed: 4-24-77

OPERATOR: CIG EXPLORATION

Depth		Formation	Remarks
From	to		
0	310	Sand-Shale	Ran 15 jts of 24# 8 5/8" csg set @ 510' Cemented w/350 sks 35/65 Posmix 6% Gel - 2% CC + 100 sks Class H w/3% CC PD @ 9:15 p.m. 4-19-77
310	739	Shale	
739	1260	Shale-Redbed	
1260	2133	Shale	
2133	2697	Shale-Lime	
2697	3150	Lime-Shale	
	3150 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief
and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II

JAMES S. SUTTON II

Subscribed and sworn to before me this 26th day of April, 1977.

Elizabeth J. Edwards

ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

