


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kearny County. Sec. 21 Twp. 21 Rge. 35 (E) (W)
Location as "NE/CNWxSWx" or footage from lines. C N/2 SW/4
Lease Owner James E. Ely
Lease Name James E. Ely Fee B Well No. 1
~~0573~~ Address c/o Warren Hotel, Garden City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-14 19 61
Application for plugging filed 1-14 19 61
Application for plugging approved 1-14 19 61
Plugging commenced 1-14 19 61
Plugging completed 1-15 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5161 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	363'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud up to 2760' Spot 100 sacks cement thru drill pipe. Heavy mud up to 300'. Spot 25 sacks thru drill pipe. Heavy mud up to 35' Halliburton plug at 35! 10 sacks cement to base cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address Sterling, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Sterling Drilling Company

(Signature) F. A. Wuellner
By: F. A. Wuellner
Sterling, Kansas
(Address)

Subscribed and sworn to before me this 16th day of January, 19 61



My commission expires Jan. 22, 1962
Bernard Luedermilk
Notary Public.

15-093-00018-0000

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- JAMES E. ELY FEE B-1
Located: C N/2 SW, Section 21-21-35, Kearny County, Kansas

OWNER: James E. Ely
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 12-22-60
COMPLETED: 1-14-61

ROTARY TOTAL DEPTH: 5161'

LOG

CASING RECORD

0 - 373	Surface Sand & Clay
373 - 480	Shale
480 - 1330	Shale & Shells
1330 - 1400	Shale
1400 - 1685	Shale & Anhydrite
1685 - 2030	Shale & Lime
2030 - 2280	Anhydrite, Lime & Shale
2280 - 3190	Shale & Lime
3190 - 3240	Lime
3240 - 3340	Lime & Shale
3340 - 3400	Lime
3400 - 3940	Lime & Shale
3940 - 4025	Lime
4025 - 4080	Lime & Shale
4080 - 4415	Lime
4415 - 4470	Lime & Shale
4470 - 4500	Lime
4500 - 4640	Lime & Shale
4640 - 4700	Lime
4700 - 4755	Lime & Shale
4755 - 4840	Lime
4840 - 4898	Lime & Shale
4898 - 5161	Lime T.D.

Set 363' of 8-5/8" surface casing
with 275 sacks cement.

Plugged and Abandoned

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1961
CONSERVATION DIVISION