

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-093-21,305

LEASE NAME Eatinger "A"

WELL NUMBER 1-17

1970 Ft. from (S) Section Line

660 Ft. from (E) Section Line

SEC. 17 TWP. 21S RGE. 35 or (W)

COUNTY Kearny

Date Well Completed 12-01-93

Plugging Commenced 12-01-93

Plugging Completed 12-01-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE#(316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-01-93 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4980'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		U	381'	8-5/8"	381'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plug and abandon using 60/40 Pozmix, 6% gel. 1st plug @ 3200' w/100 sks; 2nd plug @ 2250' w/50 sks; 3rd plug @ 1100' w/50 sks; 4th plug @ 700' w/40 sks; 5th plug @ 410' w/50 sks; 6th plug @ 40' w/10 sks. 15 sacks in rathole and 10 sacks in mousehole. Plugging complete 12-01-93.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 110 S. Main, Suite 500, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 110 S. Main, Suite 500, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 15 day of December, 19 93

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 15 1993
 CONSERVATION DIVISION
 WICHITA, KANSAS
[Signature]
 Notary Public

My Commission Expires: January 18-96