


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 27 Twp 6S Rge. 25W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW NE NW
Lease Owner D N B DRILLING, INC.
Lease Name Conkright 'C' Well No. 2
Office Address 701 First Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-5 1973
Application for plugging filed 10-5- 1973
Application for plugging approved 10-5 1973
Plugging commenced 10-5 1973
Plugging completed 10-5 1973
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4528 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Fluid	Surface	300	8-5/8"	292	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 750, plug, 50 sx cement;
Fluid to 280', plug, 25 sx cement;
Fluid to 40', plug, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
Address 701 First Nat'l Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1973

Ella Priess

My commission expires August 25, 1976

Ella Priess

Notary Public.

Ella Priess
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

D N B DRILLING, INC.
 No. 2 Conkright 'C'
 NW NE NW, Sec. 27-16S-25W
 Ness County, Kansas

Elevation: 2550 K.B.

Commenced: 9-29-73
 Completed: 10-5-73

Surface Casing: 292' of 8-5/8"
 cemented w/225 sx cement, 3% cc.
 9-28-73

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 300
Shale	300 - 635
Shale & Sand	635 - 1301
Blaine Anhydrite	1301 - 1317
Shale, Sand, Red Bed	1317 - 1735
Red Bed	1735 - 1918
Stone Corral Anhy	1918 - 1949
Shale	1949 - 2590
Lime & Shale	2590 - 4045
Lime	4045 - 4528 T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 12 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 10th day of October 1973.

My Commission Expires:
 August 25, 1976

Ella Priess
 Ella Priess, Notary Public

Ella Priess
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Com. Expires Aug. 25, 1976