

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-21,672-00-00

LEASE NAME Dodrill

WELL NUMBER #1

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. TWP. RGE. (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 10-17-88

Plugging Completed 10-21-88

LEASE OPERATOR Palomino Petroleum

ADDRESS Rt. #5, Box 51-C, Newton, Kansas

PHONE# (316-283-0232- OPERATORS LICENSE NO. 5161

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 12, 1988 (date)

by Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 4477'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	310'	None
				4-1/2"	4466'	2,505.59'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Shot casing at 3000' and 2500'. Pulled 66 joints of 4-1/2" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 10 sacks gel, 100# hulls, 150 sacks cement. Maximum pressure was 700 psi and shutin 100 psi. Dumped sand 4410' and 4 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24th day of October, 19 88

Jonas M. Leatherman
 Notary Public

My Commission Expires



STATE CORPORATION COMMISSION
 OCT 25 1988
 10-25-88
 CONSERVATION DIVISION
 Wichita, Kansas

R. A. Guard Log

15-135-2672-00-00

FILE NO.	COMPANY PALOMINO PETROLEUM				
	WELL #1 DODRILL				
	FIELD				
	COUNTY NESS	STATE KANSAS			
	LOCATION: NW-SE-SW	OTHER SERVICES			
	SEC 27 TWP 16S RGE 25W	BOTTOM GAMMA RAY			
Permanent Datum GROUND LEVEL		Elev. 2514		Elevations:	
Log Measured from KELLY BUSHING, 5 Ft. Above Permanent Datum		KB	2519		
Drilling Measured from KELLY BUSHING		DF			
		GL	2514		
Date	8-11-79	GAMMA RAY	NEUTRON	GUARD	CALIPER
Run No.	ONE	ONE	ONE	ONE	ONE
Depth-Driller	4476	4476	4476	4476	4476
Depth-Logger	4472	4472	4472	4472	4472
Bottom Logged Interval	4463	4472	4467	4460	
Top Logged Interval	00	00	3500	3500	
Casing - Driller	@	@	8 5/8 320	@	
Casing-Logger			8 5/8 320		
Bit Size			7 7/8		
Type Fluid in Hole			STARCH		
			DRIG. MUD		
Density and Viscosity			9.6 52		
pH and Fluid Loss		cc	6.8 21.2 cc		cc
Source of Sample			FLOW LINE		
Rm @ Meas. Temp.	@	°F	@	°F	@
Rmf @ Meas. Temp.	@	°F	@	°F	@
Rmc @ Meas. Temp.	@	°F	@	°F	@
Source of Rmf and Rmc			CHARTS		
Rm @ BHT	@	°F	@	°F	@
Time Since Circ.			2 HOURS		
Max. Rec. Temp. Deg. F		°F		°F	
			114 °F		
Equip. No. and Location			22 HAYS		
Recorded By			B. FARMER & R. WOLF		
Witnessed By			MR. BOB WATCHOUS		

