


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 34 Twp. 16 Rge. 25 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW of C SW SW
Lease Owner DuPont Oil Company
Lease Name WEBSTER Well No. 2
Office Address 660 Edgewater Road, Wichita, KS 67230
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed April 21 1980
Application for plugging filed (Verbally) April 21 1980
Application for plugging approved (Verbally) April 21 1980
Plugging commenced April 21 1980
Plugging completed April 21 1980
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plot

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug at 1150' with 70 sacks,
2nd plug at 240' with 20 sacks,
3rd plug 40' solid bridge with 10 sacks.
Plug was down at 6:00 a.m., 4-21-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1980



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires

RECEIVED
STATE CORPORATION COMMISSION

MAY - 1 1980

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

DuPont Oil Company
Abercrombie Drilling, Inc.
WEBSTER #2
NW of C SW SW, Section 34-16-25
Ness County, Kansas
4-11-80
4-21-80

0	60	Sand
60	1887	Sand & Shale
1887	1917	Anhydrite
1917	2032	Sand & Shale
2032	2426	Shale & Red Bed
2426	2726	Sand & Shale
2726	2918	Shale & Shells
2918	3160	Shale
3160	3549	Lime & Shale
3549	3776	Shale & Lime
3776	3848	Lime & Shale
3848	3872	Shale & Lime
3872	4510	Lime & Shale
4510	4523	Lime
	4523	Rotary Total Depth

Spud hole at 2:45 p.m., 4-11-80. Drilled 300' of 12-1/4" hole. Ran 7 joints of 8-5/8"-20# casing. (Tally 291.74). Set at 297.99'. Cemented with 200 sacks of common, 2% gel, 3% Ca.Cl. Cement by Sun Cement. Cement did circulate. Plug was down at 11:00 p.m., 4-11-80.

R.T.D. 4523'. Set 1st plug at 1150' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug 40' solid bridge with 10 sacks. 50/50 posmix, 6% gel. Job was complete at 6:00 a.m. 4-21-80.

SAMPLE TOPS:

Anhydrite 1888'
B/Anhydrite 1917'

RECEIVED
STATE CORPORATION COMMISSION

MAY - 1 1980

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WEBSTER #2, NW of C SW SW, Section 34-16-25, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 29th day of April, 1980.

SHERRIE L. BROOKS
Sedgwick County, Ks.
My Appt. Exp. 8-21-82

Sherrie L. Brooks
Sherrie L. Brooks, Notary Public