

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6534
Name: Robert Schindler
Address 1: P.O. Box 92
Address 2: _____
City: Madison State: KS Zip: 66860 + 0092
Contact Person: Robert Schindler
Phone: (620) 437-2525
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 2486 Bottom: 2608 T.D. 2635
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 017-20-230
Spot Description: _____
SE NE NW Sec. 36 Twp. 22 S. R. 9 East West
990 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chase
Lease Name: Big Springs A, B, C Well #: B-1
Date Well Completed: 7/6/1981
The plugging proposal was approved on: 8/19/2011 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 9/6/2011
Plugging Completed: 9/14/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Soil & Clay	Fresh water	Surface	8 5/8	65	None
Bartlesville	Saltwater	Production	4 1/2	2630	1247

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged back to 2480 with sand and put 4 sx cement on top of it. The fillup was 30' so 2 more sx of cement were added. Pulled 1247' of pipe. Ran 267.7 of 2 7/8 tubing and cemented to surface with 115 sx 60/40 poz with 4 % gel. The hole stayed full.

RECEIVED
MAR 28 2012

Plugging Contractor License #: 6112 Name: Long Drilling Co., LLC
Address 1: P.O. Box 131 Address 2: _____
City: Hamilton State: KS Zip: 66853 + 0131
Phone: (620) 678-3461
Name of Party Responsible for Plugging Fees: Robert Schindler
State of Kansas County, Greenwood, ss.
Robert Schindler Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert Schindler

AR