

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6534
Name: Robert Schindler
Address 1: P O Box 92
Address 2: _____
City: Madison State: KS Zip: 66860 + 0092
Contact Person: Robert Schindler
Phone: (620) 437-2525
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: ~~SWD Permit # CD 68222~~
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Tonganoxie Depth to Top: 1500 Bottom: 1665 T.D. 1665
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 017-300640002
Spot Description: NE SW NE 25-22S-9E
NE - SW. NE. Sec. 25 Twp. 22 S. R. 9 East West
1,650 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chase
Lease Name: Big Springs A, B, C Well #: SWD-1
Date Well Completed: 8-9-1981
The plugging proposal was approved on: 8-19-2011 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 9-25-2011
Plugging Completed: 9-27-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Tonganoxie	Saltwater	Cemented 100'	7"	1664	Cemented in
Surface	Freshwater	Cemented 250'	9"	301	Cemented in
Tonganoxie	Saltwater	Cemented to surface	4 1/2"	1400	Cemented in

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rigged up and washed down to 1583. Mixed 60 sx class A cement with 2% cacl, 2% gel. The mix was displaced with 4.5 bbl fresh water. Tubing was pulled out and let set 2 hrs. Ran tubing back in and tagged at 920'. Picked tubing up to 352' and cemented with 50 sx of cement. Pulled tubing out and topped-off.


RECEIVED

MAR 28 2012

Plugging Contractor License #: 6112 Name: Long Drilling Co., LLC **KCC WICHITA**
Address 1: PO Box 131 Address 2: 2035 Virgil Rd
City: Hamilton State: KS Zip: 66853 + 0131
Phone: (620) 678-3461

Name of Party Responsible for Plugging Fees: Robert Schindler
State of Kansas County, Greenwood, ss.
Robert Schindler Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

AK

STENCILED

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL


DEC 16 1967

COMPANY SUNFAY DX OIL
FARM Leedy NO. WS-1

SEC. 25 T. 22 R. 9E
LOC. APP NE SW NE

TOTAL DEPTH 1665
COMM. 9-20-66 COMP. 11-17-66
SHOT OR TREATED
CONTRACTOR Jackman & Jackman
ISSUED 12-16-67

COUNTY Chase
KANSAS



CASING
20 10 9" @ 301' w/250 sx
15 8 7" @ 1664' w/100 sx
12 6
13 5

ELEVATION NONE

PRODUCTION WTR SUPPLY
RATE SATISFACTORY
(DOUG SAND 1515-50)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SAMPLE

Tarkio 668
Reading Lime 713
Heebner 1300
Douglas Sand 1508
Total Depth 1665

RECEIVED
MAR 28 2012
KCC WICHITA

K. G. S. LIBRARY