

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-4  
March 2009

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

OPERATOR: License #: 31930  
Name: Blue Ridge Petroleum Corporation  
Address 1: PO Box 1913  
Address 2: \_\_\_\_\_  
City: Enid State: OK Zip: 73702 + 1913  
Contact Person: Jonathan Allen  
Phone: (580) 242-3732  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 057-20790-00-00  
Spot Description: \_\_\_\_\_  
SE NW NW SE Sec. 9 Twp. 27 S. R. 24  East  West  
2,217 Feet from  North /  South Line of Section  
2,149 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ford  
Lease Name: Cheyenne Well #: 5-9  
Date Well Completed: 4/3/12  
The plugging proposal was approved on: 3/30/12 (Date)  
by: Richard Lacy (KCC District Agent's Name)  
Plugging Commenced: 4/2/12  
Plugging Completed: 4/3/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	424	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 250 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal per sacks, 1st plug @ 1570' with 50 sacks, 2nd plug @ 820' with 80 sacks, 3rd plug @ 460' with 50 sacks, 4th plug @ 60' with 20 sacks, 30 sacks for rat hole, 20 sacks for mouse hole, by Basic (Ticket #06052), job was complete @ 12:15 am on 4/3/2012.

Plugging Contractor License #: 33350 Name: Southwind Drilling  
Address 1: 8 North Main Address 2: PO Box 276  
City: Ellinwood State: KS Zip: 67526  
Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: Blue Ridge Petroleum Corporation

State of Kansas County, Barton, ss.

Jill Wahlmeier  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
APR 09 2012

KCC WICHITA

Handwritten mark



Southwind Drilling, Inc.  
Plugging Orders & Reports

Lease: Cheyenne #5-9

Plugging Received from KCC Representative:

Name: Richard Lacy Date: 3/30/12 Time: 8:45 AM

1 <sup>st</sup> plug @	<u>1570</u> feet,	<u>50</u> sacks	Stands	_____
2 <sup>nd</sup> plug @	<u>820</u> feet,	<u>80</u> sacks	Stands	_____
3 <sup>rd</sup> plug @	<u>460</u> feet,	<u>50</u> sacks	Stands	_____
4 <sup>th</sup> plug @	<u>60</u> feet,	<u>20</u> sacks	Stands	_____
5 <sup>th</sup> plug @	_____ feet,	_____ sacks	Stands	_____

Mousehole: 20 sacks

Rathole: 30 sacks

Total Cement Used: 250 sacks

Type of cement: 60/40 4% 1/4" F.S. 2/5X

Plug Down @ 12:15 AM 4/3/12

Call KCC When Completed:

Name: Kevin Kenny Sullivan Date: 4/3/12 Time: 10 AM

RECEIVED  
APR 09 2012  
KCC WICHITA