

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 08060  
Name: Zenergy, Inc.  
Address 1: One Warren Place  
Address 2: 6100 S. Yale, Suite 1700  
City: Tulsa State: OK Zip: 74136 + \_\_\_\_\_  
Contact Person: Keith Hill  
Phone: (918) 488-6424  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Morrow Depth to Top: 5890' Bottom: 5914' T.D. \_\_\_\_\_  
Chester Depth to Top: 5995' Bottom: 6360' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 119-20758 . 00 . 00  
Spot Description: 660' FNL & 1980' FWL  
N/2 S/2 NE NW Sec. 6 Twp. 35 S. R. 26  East  West  
660 4620 Feet from  North  South Line of Section  
1-980 3300 Feet from  East  West Line of Section  
GPS-KCC  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Meade  
Lease Name: Ediger Well #: 2-6  
Date Well Completed: 6/26/1987  
The plugging proposal was approved on: 03/28/2012 (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Plugging Commenced: 04/02/2012  
Plugging Completed: 04/02/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface Alluvium	Fresh Water	Conductor	20"	135'	0
Surface Alluvium	Fresh Water	Surface	8-5/8"	1375'	0
Chester	Oil-Gas-Water	Production	5-1/2"	6400'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP set at 5850' + 2 sxs cement  
CIBP set at 4550' + 2 sxs cement  
Perf. 1400' + 300 sxs 60/40 poz cement with 4% gel, circulate cement to surface.

Plugging Contractor License #: 34069 Name: Basic Energy Services  
Address 1: P. O. Box 10460 Address 2: \_\_\_\_\_  
City: Midland State: TX Zip: 79702 + \_\_\_\_\_  
Phone: (432) 620-5528  
Name of Party Responsible for Plugging Fees: Zenergy, Inc.  
State of Oklahoma County, Tulsa, ss.  
Keith Hill  Employee of Operator or  Operator on above-described well,  
(Print Name)  
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: \_\_\_\_\_

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
APR 09 2012  
KCC WICHITA