

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34311
Name: JAK Oil, LLC
Address 1: 17050 390th Ave.
Address 2: _____
City: Ellis State: KS Zip: 67637 + _____
Contact Person: James Kohl
Phone: (785) 726-4667
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 3966 Bottom: 4080 T.D. 4080
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-20607-00-00 KCC
Spot Description: _____
NE NW SE NW Sec. 33 Twp. 11 S. R. 22 East West
3,795 Feet from North / South Line of Section
3,465 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Trego
Lease Name: Flagler Well #: 2
Date Well Completed: 1/13/1980
The plugging proposal was approved on: 9/28/2010 (Date)
by: Richard Williams (KCC District Agent's Name)
Plugging Commenced: 3/12/2012
Plugging Completed: 3/13/2012

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|-------------------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| Marmaton | Oil 97%, Water 3% | Production | 4 1/2" | 4065' | None |
| | | | | | |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 2 shots per foot each @ 2420', 1840', 1000'. Ran tubing to 3830', spot 4 sxs gel, followed with 50 sxs cmt w/200 hulls. Pulled tbg to 2505', spot 83 sxs cmt w/200 hulls. Pulled tbg to 1295', circulated with 80 sxs cmt. Pulled all tbg & topped off casing w/45 sxs cmt. Tied to annulus and squeezed w/15 sxs cmt to 500 psi. Plug down @ 1:00 pm. Total of 273 sxs 60/40 Poz, 4% Gel, 4 sxs gel & 400 hulls.

Plugging Contractor License #: 32810 Name: Professional Pulling services, LLC
Address 1: PO Box 486 Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-7443
Name of Party Responsible for Plugging Fees: James Kohl
State of Kansas County, Ellis, ss.
Roger L. Moses Agent Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Roger L. Moses

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 13 2012
KCC WICHITA